Each

Date: JJser:

Monday, 10/22/2007 3:59:57 PM

Kim Johnston

**Process Sheet** 

**Drawing Name** 

Part Number

Material

**Due Date** 

**Drawing Number** 

Project Number

**Drawing Revision** 

: SPACER

: D32783

: 11/5/2007

: N/A

: D3278 REV C

Customer

: CU-DAR001 Dart Helicopters Services

Job Number : 35312

: 1,1167 **Estimate Number** 

P.O. Number This Issue

NA : 10/22/2007

Prsht Rev.

First Issue : 34956 Previous Run

Written By

Checked & Approved By Comment

: Est.

04.04.19 New issue KJ/JLM

S.O. No. : NA

B 07.09.06 Rev C dwg EC Verified by: JLM Est

: SMALL /MED FAB

**Additional Product** 

Job Number:



Seq. #:

Machine Or Operation:

Description:

Black Delrin Sheet .125

1.0

MDELRINS0125



7.4005

2.8896 sf(s)

Total:

Black Delrin

Material: Black Delrin/UHMW 0.125" thick

0.0361 sf(s)/Unit

(M-DELRIN-S0.125x30.0) Identify for D327,8-3

Batch: MIS60

2.0

WATER JET





Comment: FLOW WATER JET

1-Cut as per Dwg D3278

Dwg Rev:\_\_\_

Prog Rev:\_\_\_

2-Deburr if necessary

3.0 QC2 INSPECT PARTS AS THEY COME OFF MACHINE



B07-10-34

Comment: INSPECT PARTS AS THEY COME OFF MACHINE

4.0

QC8

SECOND CHECK



Comment: SECOND CHECK

## **Dart Aerospace Ltd**

W/O:		WORK ORDER C	WORK ORDER CHANGES						
DATE	STEP	PROCEDURE CHANGE	Ву	Date	Qty	Approval Chief Eng / Prod Mgr	Approval QC Inspector		
	\$ .								
	,								
Part No	):	PAR #: Fault Category:	NCR: Yes	(No) DQ	A: <u></u>	Date: _	02/11/02		

QA: N/C Closed: \_\_\_\_ Date: \_\_

NCR:		WORK ORDER NON-CONFORMANCE (NCR)								
		Description of NC		Corrective Action Section B		Varification				
DATE	STEP	Section A	Initial Chief Eng	Action Description Chief Eng	Sign & Date	Verification Section C	Approval Chief Eng	Approval QC Inspecto		
					·		ļ			
•								-		
		,								

NOTE: Date & initial all entries

Monday, 10/22/2007 3:59:57 PM Date: User: Kim Johnston **Process Sheet** Drawing Name: SPACER Customer: CU-DAR001 Dart Helicopters Services Job Number: 35312 Part Number: D32783 Job Number: Description: Seq. #: **Machine Or Operation:** SMALL & MEDIUM FAB RESOURCE 1 SMALL FAB 1 5.0 Comment: SMALL & MEDIUM FAB RESOURCE 1 1-C'sink as per dwg D3278 2-Deburr 6.0 QC5 aspor Comment: INSPECT WORK TO CURRENT STEP PACKAGING RESOURCE #1 7.0 PACKAGING 1 Comment: PACKAGING RESOURCE #1 Identify and Stock Location: 8.0 QC21

Comment: FINAL INSPECTION/W/O RELEASE

U St. ((.02

Job Completion

### **Dart Aerospace Ltd**

W/O:		WORK ORDER CH	HANGES				
DATE	STEP	PROCEDURE CHANGE	Ву	Date	Qty	Approval Chief Eng / Prod Mgr	Approval QC Inspector
Part No		DAD #1 Foult Cotogony	NOD: Yes				

Part No:	PAR #:	Fault Category:	NCR: Yes No	DQA:	Date:	
			QA: N/C	Closed:	Date:	

NCR:		WORK ORDER NON-CONFORMANCE (NCR)							
		Description of NC		Corrective Action Section B		Verification	Annewal	Approval QC Inspector	
DATE	STEP	Section A	Initial Chief Eng	Action Description Chief Eng	Sign & Date	Section C	Approval Chief Eng		

NOTE: Date & initial all entries

DART AEROSPACE LTD	Work Order:	35312
Description: Spacer	Part Number:	D3278-3
Inspection Dwg: D3278 Rev: C		Page 1 of 1

### FIRST ARTICLE INSPECTION CHECKLIST

X First Article	Prototype
-----------------	-----------

Drawing Dimension	Tolerance	Actual Dimension	Accept	Reject	Method of Inspection	Comments
1.98	+/-0.030	1.98	¥.			,
1.98	+/-0.030	1.98	4			
1.480	(+/-0.005)	1.480	Х			
0.250	+/-0.010	,250	*			
1.480	(+/-0.005)	1.480	X.		,	
0.250	+/-0.010	· 350	Þ			
Ø0.098	+0.005/-0.000	, 099	*			
R0.13	+/-0.030	13	*			
0.125	+/-0.010	(193	¥			
					,	
					·	
-						
	,					
	,					
					,	
					<u> </u>	

Measured by:	B	Audited by:	5	Prototype Approval:	N/A
Date:	6-01-10	Date:	07/10/25	Date:	N/A


Rev	Date	Change	Revised by	Approved
Α	04.04.19	New Issue P/O D3278-041	KJ/JLM	
В	06.03.09	Dwg Rev updated	KJ/JLM	
С	07.02.02	Dwg updated per JLM	KJ/JLM	
D	07.09.26	Dimensions updated per Dwg Rev. C	KJ/EC	B
	<del></del>	· · · · · · · · · · · · · · · · · · ·		



	•							
	DESIGN PI DRAWN BY			DART AEROSPACE LTD HAWKESBURY, ONTARIO, CANADA				
1	CHECH	(ED	APPROVED,	DRAWING NO.	REV. C			
		_#	#	D3278 SHEET	1 OF 3			
	DATE		- 4	TITLE	SCALE			
	07.0	7.24		SUPPORT ASSEMBLY	NTS			
	Α		04.03.03	NEW ISSUE				
	В		05.03.31	CHANGE DIM/TOL TO ENSURE FIT				
	С		07.07.24	CHANGED RIVETS PER PAR #185	,			



# D3278-041 SUPPORT ASSEMBLY



Qty	Part Number	Description	
Х	D3278-041	SUPPORT ASSEMBLY	
2	D2230-1	CLAMP	
1	D3278-1	SUPPORT	
1	D3278-2	SUPPORT	
1	D3278-3	SPACER.	
			<u>U</u> }
2	AN4-13A	BOLT	
4	AN960JD416	WASHER	
4	MS20426AD3-6	RIVET *	
2	MS21042L4	NUT	


SHOP COPY RETURN TO ENGINEERING CONTROLLED COPY BJECT TO AMENDMENT WITHOUT NOTICE WORK ORDER

Copyright © 2004 by DART AEROSPACE LTD

THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.



DESIGN	DRAWN BY	DART AEROSPACE LTD HAWKESBURY, ONTARIO, CANADA	
CHECKED	APPROVED	DRAWING NO.	REV. C
A	-#	D3278	SHEET 2 OF 3
DATE		TITLE	SCALE
07.07.24		SUPPORT ASSEMBLY	1:1



### D3278-1 SUPPORT (SHOWN) D3278-2 SUPPORT (OPPOSITE)

- 1) MACHINE PER DWG FILE "D3278-1.SLDPRT"
- 2) MATERIAL: 6061-T6 (OR 6061-T651/T6510/T6511/T62) BAR

PER AMS-QQ-A-225/8 (OR AMS 4117/4128/4115/4116) SHOP COPY

PER AMS-QQ-A-200/8 (OR AMS 4160)

(REF. DART SPEC. M6061T6B)

3) FINISH: CHEMICAL CONVERSION COAT PER DART QSI 005 4.1 POWDER COAT WHITE (4.3.5.1) PER DART QSI 005 4.3

- 4) BREAK ALL SHARP EDGES 0.005 TO 0.015
- 5) TOLERANCES ARE PER DART QSI 018 UNLESS OTHERWISE NOTED
- 6) ALL DIMENSIONS ARE IN INCHES UNLESS OTHERWISE NOTED


RETURN TO **ENGINEERING** UNCONTROLLED COPS SUBJECT TO AMENDMENT WITHOUT NOTICE WORK ORDER


Copyright @ 2004 by DART AEROSPACE LTD

THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.



	DESIGN	DRAWN BY	DART AEROSPACE LTD HAWKESBURY, ONTARIO, CANADA		
Ì	CHECKED	APPROVED,,	DRAWING NO.	REV. C	
1	一书	<del>-   </del>	D3278	SHEET 3 OF 3	
ľ	DATE		TITLE	SCALE	
ı	07.07.24		SUPPORT ASSEMBLY	1:1	





#### **D3278-3 SPACER**

1) MATERIAL: DELRIN II 150E OR ACETRON GP ACETAL (REF. DART SPEC. M-DELRIN-B0.125x2.000) OR

DELRIN II 150E OR ACETRON GP ACETAL (REF. DART SPEC. M-DELRIN-S.125)

2) BREAK ALL SHARP EDGES 0.005 TO 0.015

3) TOLERANCES ARE PER DART QSI 018 UNLESS OTHERWISE NOTED

4) ALL DIMENSIONS ARE IN INCHES UNLESS OTHERWISE NOTED

SHOP COPY
RETURN TO
ENGINEERING
UNCONTROLLED CO
SUBJECT TO AMENDME
WITHOUT NOTICE
WORK ORDER

WORK ORDER 35312

Copyright © 2004 by DART AEROSPACE LTD

THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.